



Customer:
City of Barrie

System:
4' and 6"
Sanitary Service Laterals

Problem



The contractor, BJ Contracting, contacted CPL after experiencing a challenge with the previous contractor not being able to update 22 sanitary lines running from residents homes on Barrie's busy Dunlop Street to the City's main sanitary drain without tearing up the street.

Solution

CPL recognized that shutting down a main thoroughfare in Barrie was not an option. After months of previous construction it would have been considered a further inconvenience to the residents and businesses. CPL proposed to Cure-in-Place-Pipe (CIPP) restore all 22 laterals using push rods rather than through traditional methods.



How did we do?



After only eight working days, CPL installed all the required liners successfully and to satisfaction of the city's contractor and the City of Barrie. This was done without causing any further disturbance to the residents of this busy traffic neighborhood.